

PRIME MINISTERS MUSEUM AND LIBRARY
Teen Murthi House New Delhi 110011

NOTICE INVITING QUOTATION (NIQ)

F.No.9-20/2025-26/Admin(pt file)

Date: 23.06.2026

Subject: Notice Inviting Quotations (NIQ) for Repair/Replacement of Red Sand Stone Flooring at PMS-I.

Sealed quotations are invited for the below-mentioned work from eligible and experienced agencies/contractors on **percentage rate basis (Above/Below DSR 2023)**.

Schedule of Quantities (SOQ)

S. No.	Description of Item	Qty	Unit	DSR Rate (₹)	Amount (₹)	DSR Code
1	Providing and laying red sand stone flooring 40 mm thick over 20 mm avg. thick cement mortar 1:5 (1 cement : 5 coarse sand) including joint finishing	250	sqm	1280.10	3,20,025.00	11.28.1
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material & disposal within 50 m lead	250	sqm	266.45	66,612.50	15.25
3	Providing cement concrete (1:2:4) (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	5	cum	7878.50	39,392.50	4.1.3

Total Estimated Cost ₹ 4,26,029.50

Rate to be Quoted by Bidder

Particulars	Percentage (%)
% Above / Below / At Par on DSR 2023	_____ %

Other Terms & Conditions

1. Rates shall be quoted **in percentage (%) only** (Above/Below DSR).
2. The quoted rate shall include all taxes, labour, material, T&P, etc.
3. Work shall be executed as per **CPWD DSR 2023& specifications**.
4. Payment will be made based on actual measurements.
5. Time of completion: **30 days**.
6. No escalation shall be admissible.
7. Competent authority reserves the right to accept/reject any quotation.

Submission of Quotation: Quotation shall be submitted in a **sealed envelope** superscribed: "**Quotation for Repair/Replacement of Red Sand Stone Flooring at PMS-I,**" and addressed to: **Director, Prime Ministers Museum & Library Teen Murti House, New Delhi – 110011.**

Quotation may be deposited at **Reception, Library/Admin Building, PMML, Teen Murti House, New Delhi.**

Last Date of Submission: 30.06.2026 up to 11:00 AM

Signature of Bidder

Name: _____

Firm Name: _____

Signature & Seal: _____

Date: _____

P-2

P-2

Schedule of Quantities						
Name of Work:- Repair/Replacement of Red sand stone of PMS- I Dg 2026-2027 ✓						
Sl. No.	Short description of item	Qty	Rate	Unit	Amount	DSR Code
1	SAND STONE FLOORING 40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand) with joints finished flush.	250	1280.10	sqm	3,20,025	11.28.1
2	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	250	266.45	sqm	66,612.50	15.25
3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	5	7878.5	cum	39,392.50	4.1.3
Total					4,26,029.50	

Pay 4,24,030/-

24/03/26

Anirudh Kumar Tyagi
(Consultant)